DAVANGERE MUNICIPALITY.

Notice dated 12th December 1927.

Notice is hereby given that sealed tenders will be received at the office of the President, Davangere Municipality up to 31st December 1927, for removing the existing 3″ main and relaying with a 4″ C. I. main in Chitaldrug Road in the Davangere Municipality. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the 31st January 1928.

2. The plans, detailed estimate and conditions may be seen at the President's Office, Davangere, between the hours of 11 A.M. and 5 P.M. on all working days.

3. Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 100 in cash as earnest money, and be superscribed "Tender for removing 3″ main and relaying with a 4″ C. I. main in Chitaldrug Road" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the President, Davangere Municipality, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within three days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond on a stamped paper, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the President's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for removing the existing 3″ main and relaying with a 4″ C. I. main in Chitaldrug Road for improving the water-supply in the Chamarajpet and Narasarajpet ridges :—

Serial No.	Items of work	Unit	Quantities
1	Earthwork excavation	100 C.ft	4,020
2	Refilling the trench after laying 4″ pipe where 3″ pipe is removed.	,,	9,375
3	Laying and jointing 4″ C. I. pipes	Cwt.	350
4	4″ lead joints	Each	254
5	4″ C. I. cuts	,,	20
6	Fixing specials	,,	12
7	Unforeseen charges	...	...
8	Removing 3″ main including earth work etc.... ...	Cwt.	170

N.B.—The materials such as pipes and other specials will be supplied from the Municipality.

S. ABDUL KHALAK,
President.

SANITATION BYE-LAWS OF THE KONANUR AND ARKALGUD MINOR MUNICIPALITIES.

Dated 1st February 1927.

The following draft bye-laws are framed by the Konanur Municipal Council under Section 48 (1) of the Municipal Regulation of 1906 and are published for the information of public.

Any resident within the area of the Konanur and Arkalgud Municipalities who has any objection or suggestion with respect to the draft bye-laws should communicate the same to the President, Konanur and Arkalgud Municipalities within one month from the date of this notification.